

Custom unit widths between 8'-7" & 9'-0"

Custom unit heights between 7'-6" & 8'-0"

Installation and Operation

door in event of power failure.

(Linear Dr. opposite side)

Power Supply

Wall Area

Type SX-P

3 1/2" (89)

Unit Width

SX

Slide/Swing

Panel

Breakout / Wall

Opening

Slide Opening

ARCHITECTURAL DETAILS

AUTOMATIC ICU / CCU ENTRANCES - AIRBORNE INFECTION CONTROL

Profiler® Series 2000-IDS-2

Smoke Rated Automatic Isolation Door System Type: 110 Single Slide Surface Appled P-SX or SX-P A10.30.2 July 19

1 7/8"

(48)

1 15/16" (49)

Standard Packages

Unit Width	Slide Opening	Breakout / Wall Opening	Slide Panel Width
8'-7" (2616)	3'-9 1/2" (1156)	4'-0 1/2" (1232)	4'-3 1/2" (1308)
9'-0" (2743)	4'- 0" (1219)	4'-3 1/2" (1308)	4'- 6" (1372)
Note: Consult factory for sizes smaller than 8'-7" (2616)			
Unit Height: 7'-6" (2286) Glazing: Standard unit prep'd for 1/4" (6) glass (by others)		Anodized Finish: Clear or Dark Bronze	
		See Arch. Specificatons. A23.1-5	
Options			

• Surface Mounted: onto exterior finish wall. Finish floor not to exceed 1/4" out of level.

Max. current draw is 3.15 amps. UPS (Uninterrupted Power Source) recommended.

• Positive Latching: Required for UL 1784 compliance. Provided by Fail-Safe Autolock.

Electrical: 120 VAC, 60 cycle, single phase, 20 amp service in conduit routed to header.

Actuator

(914)

3'-0"

Exterior Elevations and Floor Plans

3/8 (1051)3-5

"Knowing Act" Activation: Touchless sensor or push plate at interior & exterior for 2-way traffic. Door closes after time delay expires and slide opening is clear. Power-Fail Close Module closes

Compliant with:

• Custom paint, anod. finish or Antimicrobial coating

Unit Width

-Power Supply for Linear & Belt Dr.

Wall Area

6

(121

4'-0" (610)

Type SX-P

SX panel can breakout

from any point of slide

travel with max. 50 lbf.

of force at lock stile

3 1/2" (89)

Safety Beams

Jnit Heigh

SX

Slide/Swing

Panel

Recessed

Breakout / Wall

Opening

Slide Opening

Pull

- 2018 FGI Guidelines for Airborne Infection Isolation Room Systems, Ref: A2.1-7.2.2.3 (2)(a)(i)
- ASTM E283-04 Standard Air Infiltration Test
 - Maintains positive/negative pressure
 - -- Perimeter seals factory installed
- UL 1784 Air Leakage Test of Door Assemblies
- NFPA 105 Std. for Installation of Smoke Door Assemblies

4" (102) 6"(152) Header Height Series 2000 Linear Drive 2000B Belt Drive Electric • Field Applied Floor Seals: 1/8" to 1/2" above finished floor as required for positive/negative pressure. Operator C264R C265R SAGR C327R Breakout Rail C335 Interlock 4 (21 Ċ C337 C338R Stop 1/2" (13) 7'-0" (2134) Muntin C337 3'-5" (1041) C336 (102)

3/8" 1/8" to 1/2" gap as req'd for

-067

Finish

Floor

Positive/Negative Pressure Vertical Section

